

LINAC Upgrade Project at the Canadian Light Source



Canadian Light Source / Centre canadien de rayonnement synchrotron
THE BRIGHTEST LIGHT IN CANADA™





Grant Cubbon:	HSE Manager
Darin Street:	Radiation Protection Lead
Brian Bower:	Radiation Protection Specialist

History

Saskatchewan Accelerator Laboratory (SAL)

- 1964 -high energy physics research facility
- 300 MeV LINAC
- ~ 2,000 m² footprint
 - Brick and mortar



Canadian Light Source

- Construction started 1999
 - 2.9 hectare footprint
 - ~ 12,000 m² building
 - 5 levels
 - Linac in SAL building
 - Booster/Storage Rings, and Beamlines in ‘new’ section of building





Canadian Centre
Light de rayonnement
Source synchrotron



UNIVERSITY OF
SASKATCHEWAN


Electron Gun and Linac

- 2 Stories underground
 - Former SAL
- 250 MeV
- 1Hz
- 6 Section
- 70 or 140 nS pulse
- Energy Compression





Booster Ring/Storage Ring

- **Booster Ring**
- 250 MeV to 2.9 GeV
- 10 mA design average current
 - 3 to 4 mA normal
- 2 Conventional RF cavities
- **Storage Ring**
- 12 straight sections
 - 9 available for insertion devices
- 170.88 m circumference
- Superconducting RF cavity




Beamlines

- 22 Operational Beamlines
- 2 diagnostic beamlines
- Infrared to Hard X-ray



CLS Linac Replacement Project

- Why Change the Linac????
 - Improved Reliability!!
 - Better Beam
 - ‘Like for Like’ Change
- Change = Opportunity
 - What else can we get from the project?
- Project touching many departments
 - Planning and Preparation
 - Dismantling
 - Installation
 - Commissioning/Testing
 - Radiation Protection/Safety input needed




'Like for Like' Change

Accelerator Physicists



Shiny New Toy



Slide courtesy Darin Street



Canadian
Light
Source Centre canadien
de rayonnement
synchrotron




'Like For Like' Change



- 250 MeV Linac
 - Same location
 - 1Hz e^- Pulse
 - Same pulse length
 - Same energy
- Like for like safety?
 - Shielding 😊
 - ACIS(lockup) 😊
 - Fire Protection 😊

LINAC



2 Stories Underground

To Synchrotron



Like For Like Change, almost...

- Single Bunch Mode – Increased current
 - Previous 0.24 nC
 - Planned 1.5 nC
 - Improved Single Bunch Mode Operation
- Injector Frequency Change
 - Previous 2856 MHz
 - Planned 3000 MHz
 - Improved Booster Ring Capture Efficiency
- Physically shorter
 - 3 sections from 6 sections
- 10 Hz E-Gun or RF operation
 - But not both!
- Removal of partial concrete wall



Safety Planning And Preparation


Regulatory

- Documentation: “Like for Like Change”
- New LINAC within Licencing envelope
- No Licencing concerns!



Worker Safety

- Hazardous Building Materials Assessment
- Residual radiation surveys
- Dismantling Plan
 - Logistics and storage
- Daily Tool-Box Meetings



Safety Lives in Conversation

Access Control and Interlock System (ACIS)


- **10 Hz E-Gun or RF operation - Not both!**
 - Improve Commissioning
 - Shielding/Occupancy reviews required
- **ACIS modifications to limit 10 Hz Operation**
 - Input signals to ACIS from timing system
 - Egun and RF System Disabled independently



ACIS Interlock Logic Diagram

AutoCAD SHX Text
1

LINAC PERMISSIVES




ACIS Zone Changes

- **Concrete Half-Wall removal**
 - Not a shielding wall for CLS
 - Change of egress path
 - Move of one ACIS gate
 - Improvement to overall egress!
- **Concrete block wall removal**
 - Redesign of ACIS zones
 - Reduced congestion, improved access to eqp



Dismantling Plan

- Detailed dismantling plan developed
 - Residual radiation level well understood
 - Max contact dose < 25 $\mu\text{Sv/h}$
 - Strict limits on disposal
 - Logistics and other details
 - Movement and storage
 - Survey records
 - Disposal process



Out with the old linac!

– Gone in 3 Days!

- 2 weeks allotted as contingency
- Radiation Surveys kept pace
- Logistics kept pace
- All due to good preparation!

– No injuries

- No minor injuries, no near misses

– Compliance

- Limits on total occupancy in linac area
- Hot work permits/requirements
- Lockout/Tagout (Control of Hazardous Energy)
- Worker PPE Requirements



Linac Hall After!



Safety Perfection?




- **Storage Issues**
 - Several storage non-conformances
 - All resolved promptly when raised
 - Reminders in daily meetings
- **Signs and Barriers**
 - Linac removal resulted in partially uncovered sump - poorly marked
- **But no big surprises...**



Communication

- Communication of work, change, and safety concerns through:
 - Daily Tool-Box Meetings
 - 8am, 3:15pm leads + Managers
 - Signs
 - ‘SLACK’ channels
 - Reporting Systems
 - Hallway meetings
 - Reinforced the message!!!



Safety Lives in Conversation

**MEETING ROOM
(STANDING ROOM
ONLY!)**



Linac Installation

- **> Two years project planning**
 - Project Management Lead Assigned
 - Large Team Effort (by CLS standards)
 - May 27 –and Commissioning Synchrotron Beam Off
 - Installation complete by Sep 9
 - 1 week behind schedule
 - Still looking promising for Jan 1, 2025 User Beam



Installation



Commissioning

- September 10 – Dec 31, 2024
 - RF Conditioning
 - Very Slow
 - Issues with components
 - Commissioning not completed



Current Status

- RF Conditioning continuing
 - Still very slow but progressing
 - Problems are understood
- Plan to achieve 180 mA from Linac by Aug 31
- User beam by October 2025?



Thank-you!

